

Executant 0005 A
 Obiectiv 01 Lucrari Sf. Gheorghe
 Obiect 09 Strada Paraului
 Categorie 01 Deviz lucrare

Deviz oferta

						[ron]
Pozitie	Cod resursa		U/M	Cantitate	Pret unitar	Valoare
Denumire resursa/ Observatii						
Corectii						
0	1	2	3	4	5	
1	TSA16C4	82	M CUB	112,0000	39,3397	4.406,04
SAP.MAN.IN TRANSEE PT.CABL.EL.IN PAM.CU UMID.NAT.C						
U SPRIJ.CU OBST.LAT.<1M,ADINC.<1,5M,T.TARE						
2	TSD18C1	82	M CUB	84,0000	16,6767	1.400,84
UMPLUT.COMPACTATA IN SANT.PT.CABL.INGROP.LA LINII						
ELECTR.DE INALTA TENS.CU PAM.DIN TEREN TARE						
3	W2H04A	99	M CUB	28,0000	95,5644	2.675,80
STRAT NISIP ASEZAT IN SANT PT. PROTEJAREA CABLELOR						
LA LUCRARI IN PROFIL NETIPIZAT						
4	TRA01A25P	82	TONE	44,8000	11,9881	537,06
TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU						
AUTOBASCULANTA DIST.=25 KM						
5	TRI1AA02C2	82	TONE	44,8000	5,9650	267,23
INCARCAREA MATERIALELOR,GRUPA A-GRELE IN BULGARI,P						
RIN ARUNCARE RAMPA SAU TEREN-AUTO CATEG.2						
6	W3K05A1	82	M	20,0000	112,0702	2.241,40
SUBTRAVERSARE CALE RUTIERA IN TUB PVC 110 MMP						
in tub PVC 110 mmp						
7	DG06XA	93	M CUB	10,0000	100,9543	1.009,54
SPARGEREA SI DESFAC.BET.DE CIM.PE SUPRAF.LIMIT.PT.						
POZARE CABLURI,COND.ETC EXEC.DIN IMBRAC.CAROSABILA						
8	DB16E1	82	MP	100,0000	81,9785	8.197,85
IMBRAC BET ASF CU AGREGAT MARUNT EXEC LA CALD IN						
GROS DE 2,5CM ASTERN MECANICA						
9	W2G01B#	99	M	380,0000	1,9442	738,78
CABL.EN.EL.ARMAT COND.AL 1KV,POZAT IN SANT PAT NIS						
IP CU TRACT.MAN,SECT.3X25+16-3X50+25MMP,FARA OBST.						
10	4806945		M	380,0000	11,7482	4.464,33
CABLU ENERGIE ACYABY 0,6/ 1KV 3X 25 + 16 M S 87						
78						
11	W2H05A	99	MP	70,0000	3,2854	229,97
BANDA PVC PT. PROTEJAREA CABLELOR IN PROFIL NETIPI						
ZAT						
12	W2I04A	99	KG	520,0000	17,4998	9.099,89
MONTARE ELECTROD ORIZONTAL DIN PLATBANDA ZINCATA P						
T. PRIZA DE PAMINT IN TEREN NORMAL						
13	W1R06A1	82	M	7,5000	68,3998	512,99
ELECTROD DIN TEAVA DE OTEL DE DOI TOLI SI JUMATATE						
PENTRU LEGAREA LA PAMINT IN TEREN NORMAL						
14	W2I06A	99	BUCATA	1,0000	2,6175	2,61
IMBINAREA PRIZEI DE LEGARE LA PAMINT CU SURUBURI Z						
INCATE						
15	W2J03A	99	BUCATA	1,0000	29,1623	29,16
VERIFICAREA PRIZELOR DE PAMINT						



Executant0005	Obiectiv01	Obi09	Cate01	[ron]		
0	1	2	3	4	5	
16	W2I01A01	82	BUCATA	10,0000	92,8111	928,11
LEGARE LA PAMINT A NULULUI SI ELEMENTELOR DE PE ST ILP RET.ELECTR.AER.1 KV CU CONDUCT.NEIZOLATE						
17	EC03A1	82	M	100,0000	6,9666	696,65
CABLU ENERGIE MONTAT CU SCOABE PE CONSOLE FIX.CU D IBLURI METAL COND.< 10 MMP.						
18	4801907		M	100,0000	5,0350	503,49
CABLU ENERGIE CY 0,6/ 1KV 3X 2,5 U S.877						
19	W2G15A	99	BUCATA	1,0000	13,4471	13,44
ASEZAREA TAMBURULUI PE CAPRA CU GREUTATEA < 500 KG						
20	ACA10D1	82	M	800,0000	43,2498	34.599,80
MONTARE TEAVA PVC IN PAMINT IN EXTERIORULCLADIRIL OR,AVIND DN 110						
canalizatie comuna						
21	ACD06A1	82	BUCATA	8,0000	1.693,9523	13.551,61
CAMIN VIZITARE BETON 800X800X800 MM (LXLXH)						
22	ACD01C1	82	BUCATA	8,0000	629,3771	5.035,01
CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE FARA PIES A SUPORT NECAROSABIL TIP II B \$						
23	TSA17C1	82	M CUB	4,4000	72,2431	317,86
SAP.MAN.GROPI POLIG.MONOBL.PT.LINII EL.PAM.CU UMID .NAT.FARA SPRIJ.LAT.<1M,ADINC.<2,5M,T.F.TARE						
24	CA01M1	82	M CUB	4,4000	69,6992	306,67
TURNARE BETON SIMPLU IN FUNDATII LA CONSTRUCTII IN GINERESTI(STILPI LEA,ETC.)						
25	2100911		M CUB	4,4000	287,7120	1.265,93
BETON MARFA CLASA C15/12 (BC15/B200)						
26	TRA06A10	82	TONE	9,6800	35,9640	348,13
TRANSPORTUL RUTIER AL BETONULUI-MORTARULUI CU AUTO BETONIERA DE 5,5MC DIST. =10KM \$						
27	W2A16A1	82	BUCATA	10,0000	162,8626	1.628,62
STILP SIMPLU TEAVA OL IN FUNDATIE TURNATA TEREN NO RMAL						
28	0909009		BUCATI	10,0000	1.498,5000	14.985,00
STALP METALIC OL-ZN H=8M						
cf fisa tehnica nr1						
29	EA01A	82	M	30,0000	13,2650	397,95
TUB PVC 63 MONTAT INGROPAT						
30	W2F08A01	82	BUCATA	10,0000	367,1680	3.671,67
CUTIE SIG.CU LOC PTR.BALAST PTR.LAMPA CU VAPORI ME RCUR MONT.AUTOTELES.CU 1 SIG.SI 1 BAL.ST.BET.						
31	EH05E1	82	BUCATA	10,0000	12,4750	124,75
INCERCARE CUTII CU CLEME \$						
32	W2F13K01	82	BUCATA	10,0000	151,1572	1.511,57
PRELUNGIRE PT.MONT.CORP ILUM.INCL.COND.INTERIOR CU 1 BRATE ST.METAL MONT.CU TELESCOP MONTAT						
33	#155099		BUCATI	10,0000	269,7300	2.697,30
CONSOLA LUNGA 1 BRAT						
conform fisa tehnica nr.1						



Executant0005	Obiectiv01	Obi09	Cate01	[ron]		
0	1	2	3	4	5	
34	W2F03E01	82	BUCATA	10,0000	53,8916	538,91
CORP DE ILUM.PROT.CONTRA APEI NEECHIPAT,TIP B 200 MONT.CU AUTOTELESCOP PE ST.BETON. MONTAT						
35	#155731		BUCATA	10,0000	1.138,8600	11.388,60
CORP DE ILUMINAT IP66 100W SODIU						
conform fisa tehnica nr.2						
36	EC11E1	82	BUCATA	40,0000	62,4452	2.497,80
CAP TERMINAL INTERIOR LEG.LA BORNE CU COND.AL. 3X 35+16 SAU 3X50+25MMP						
37	W2E05D01	82	BUCATA	1,0000	110,1365	110,13
TABLOU DISTRIB MONT IN FIRIDA PE STEL.MET CU MPR 5 00 V 315 A CU 2 CIRC TRIF SI CL.NUL ZID BETON						
38	#155022		BUCATA	1,0000	6.593,4000	6.593,40
CUTIE DE DISTRIBUTIE CU 4 CIRCUITE						
39	W2E20B	99	BUCATA	1,0000	3,5643	3,56
RACORDAREA CIRCUITELOR ELECTRICE IN TABLOURI LA BO RNE CU SECTIUNEA 10-16 MMP						
40	W2J03B1	82	BUCATA	1,0000	120,6997	120,69
SCOAT DE SUB TENS A RET IN VEDEA REP SI RAC BRANS A RETELEI SUBTERANE						
41	W2J04A	99	BUCATA	1,0000	35,3188	35,31
VERIFICAREA SI INCERCAREA TABLOURILOR,FIRIDELOR DE DISTRIB.,CUTIILOR DE DISTRIB.						
42	EH01A1	82	BUCATA	1,0000	48,4390	48,43
INCERCAREA CABLURILOR DE ENERGIE ELECTRICA DE MAXI MUM 1 KV. \$						
43	W2J02A1	82	BUCATA	1,0000	132,8614	132,86
VERIFIC SI INCERC RET ELC SUBT.CU CABLU NOU						
44	TRA01A10	82	TONE	1,0000	599,4000	599,40
TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELO R CU AUTOBASCULANTA PE DIST.= 10 KM. \$						
Total fara T.V.A.						140.466,34
T.V.A.						33.711,92
TOTAL OFERTA						174.178,26

OFERTANT